




GARIBALDI



THE EXISTING PROJECT

The existing project provides for a channel 18 feet deep and of suitable width across the ocean bay to deep water in the bay, and thence a channel 18 feet deep and 200 feet wide to a turning basin 18 feet deep and 500 feet wide in Miami Cove.

Also provided for a small boat basin and approach 12 feet deep at Garibaldi.

The turning basin in Miami Cove is presently not maintained.

NOTES:

Horizontal Coordinate System:
North American Datum of 1983 (NAD83), projected to the State Plane Coordinate System (SPCS), Oregon North Zone. Distance units in U.S. Survey Feet.

Vertical Datum:
Soundings are shown in feet and indicate depths below Mean Lower Low Water (NAD83-2001, MLLW is 0.41 feet below the North American Vertical Datum (NAVD 88) at Garibaldi boat basin.

River mileage conforms to the River Mile Index of the Hydrology and Hydraulics Committee, Pacific Northwest River Basins Commission, July 1972.

The information depicted on this map represents the results of a survey conducted on the date indicated and can only be considered to represent the general channel conditions existing at that time and is in support of channel maintenance only.

** Shoals Sounding per Quarter Per Reach

STAFF GAGE AT FUEL DOCK GARIBALDI MARINA:

Condition: ☐ PREDREDGE ☐ POSTREDGE

LEGEND

- | | | |
|--|--|--|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

2009 Aerial Photography data source: U.S.D.A., Service Center Agencies - Reference is Navigation Chart No. 18558

TILLAMOOK BAY
& BAR

GARIBALDI BOAT BASIN ENTRANCE

25 March 2021

Scale in Feet

0 100 200 300 400 500

SUBMITTED: _____ APPROVED: _____

RECOMMENDED: _____ CHIEF, WATERWAYS MAINTENANCE SECTION

CHIEF, SURVEY SECTION SURVEYED: _____ PLOTTED: _____ CHECKED: _____

TM 04_GBB_20210325_CS